BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.169

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/02/2012-13 Dated: 15-05-2012

Name of Work: Construction of Moulded drain in Kuvempunagara 1st stage Near Samudhaya Bhavana roads in Ward No. 11, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Hombe Gowda	
				In Figures	In Words
1	85.86	Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	65.98	Rupees Sixty Five and Ninety Eight Paise Only
2	33.26	Providing and laying in position **plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs** using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, etc complete as per specifications and directions of engineer in charge of the work	Cum	4134.80	Rupees Four Thousand One Hundred Thirty Four and Eighty Paise Only
3	8.64	Providing and constructing granite / trap / basalt size stone masonry in **foundation cement mortar 1:6**, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	2968.13	Rupees Two Thousand Nine Hundred Sixty Eight and Thirteen Paise Only
4	1.08	Providing and laying in position plain cement concrete of **mix M15 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4683.67	Rupees Four Thousand Six Hundred Eighty Three and Sixty Seven Paise Only
5	14.40	Providing flush pointing to square rubble, course or uncoursed stone masonry with **cement mortar 1:3,** 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	79.60	Rupees Seventy Nine and Sixty Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Hombe Gowda	
				In Figures	In Words
6	381.51	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	232.38	Rupees Two Hundred Thirty Two and Thirty Eight Paise Only
7	29.42	Providing and laying in position **reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5559.47	Rupees Five Thousand Five Hundred Fifty Nine and Forty Seven Paise Only
8	22.07	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qntl	7712.27	Rupees Seven Thousand Seven Hundred Twelve and Twenty Seven Paise Only
9	4.65	Providing and laying in position plain cement concrete of **mix M20 with OPC cement @ 300 kgs, with 20mm** and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5237.08	Rupees Five Thousand Two Hundred Thirty Seven and Eight Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Hombe Gowda	
				In Figures	In Words
10	213.75	Construction of embankment with approved materials Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. which includes cost of gravel / Murrum, watering charges & compaction by vibratory roller) etc complete as per specifications and directions of engineer in charge of the work	Cum	154.17	Rupees One Hundred Fifty Four and Seventeen Paise Only
11	128.25	Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1113.16	Rupees One Thousand One Hundred Thirteen and Sixteen Paise Only
12	855.00	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	10.54	Rupees Ten and Fifty Four Paise Only
13	855.00	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	42.60	Rupees Forty Two and Sixty Paise Only
14	21.38	Providing and laying **semi dense bituminous concrete** 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. **With 80/100 grade bitumen,** etc complete as per specifications and directions of engineer in charge of the work	Cum	9322.88	Rupees Nine Thousand Three Hundred Twenty Two and Eighty Eight Paise Only

Sl. No	Approved Qty.	Description	Unit	Approved Tender Rates of Hombe Gowda	
				In Figures	In Words
15	85.86	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	75.95	Rupees Seventy Five and Ninety Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92